

HIGH CAPACITY | PRECISION | RELIABILITY

Plasser & Theurer

Digital Transformation of Railway Infrastructure

Stefan Damm, CEO DMA (Italy)
Jochen Nowotny, CEO tmc (Austria)



Track Machines Connected

We ♥ Railways

FOUNDED IN

2019

3 SITES

Austria & India

EMPLOYEES

96

The IT branch
of world market leader
Plasser & Theurer:
**High-tech in the
Niche**

Coming from Austria,
the **#4 export
country in rail
technology**

You are no Beta-
Tester: **Quality
Assurance
on our machines
and tracks**

Software Suite tmOS
understands
**Lifecycle
Management,
Obsolescence and
Cybersecurity**

DMA s.r.l. – Accurate & Reliable

Plasser & Theurer

Part of Plasser & Theurer since 2023



DMA Diagnostics
A Plasser & Theurer Company


01 Digital Environmental Twin

High-precision colored Point Clouds



Project Offenburger Railway Line, Germany

Plasser & Theurer



Project Riedbahn Railway Line, Germany

Plasser & Theurer



Digital full-service process


Making a Point cloud useful



Track Survey

MEASUREMENT CARS,
TROLLEYS, FLAT WAGONS

1. Central start & stop
2. Capture & process
3. Upload to backoffice



Generation of highly precise Point Cloud & AI-based Data Analytics

BACKOFFICE

1. Visualization
2. AI - application
3. Analysis & measurements

Digitale erfassen - Übersicht						
Station (Tress)	Beschreibung	Rechtswert	Neutwert	Höhe	Abstand (Tress)	Notendifferenz %
10106 870707	Beginn Kabelkanal links (K70 aus E270) nicht umgesetzt, s = 40 cm, Gleisbau	5403600.07	5403600.07	101.0	-5.388	-0.124
10106 881201	Kabelkanal links (K70 aus E270) nicht umgesetzt, s = 40 cm, Gleisbau	5403600.76	5403600.76	101.08	-2.098	-0.049
10106 881725	Kabelkanal links (K70 aus E270) nicht umgesetzt, s = 40 cm, Gleisbau	5403600.57	5403600.57	101.02	-4.009	-0.11
10106 101009	Kabelkanal links (K70 aus E270) nicht umgesetzt, s = 40 cm, Gleisbau	5403600.59	5403600.59	101.0	-4.015	-0.029
10106 340948	Kabelkanal links (K70 aus E270) nicht umgesetzt, s = 40 cm, Gleisbau	5403600.81	5403600.81	101.01	-3.323	-0.116
10206 100749	Ende Kabelkanal links (K70 aus E270) nicht umgesetzt, s = 40 cm, Gleisbau	5403607.09	5403607.09	101.0	-3.052	-0.111
10206 100851	Beginn Kabelkanal links (K70 aus E270) nicht umgesetzt, s = 40 cm, Gleisbau	5403607.08	5403607.08	101.0	-3.062	-0.111
10212 400404	Kabelkanal links (K70 aus E270) nicht umgesetzt, s = 40 cm, Gleisbau	5403607.03	5403607.03	101.0	-3.712	-0.400
10212 750901	Beginn Kabelkanal links (K70 aus E270) nicht umgesetzt, s = 40 cm, Gleisbau	5403607.03	5403607.03	101.0	-3.712	-0.400
10215 340205	Kabelkanal links (K70 aus E270) nicht umgesetzt, s = 40 cm, Gleisbau	5403607.08	5403607.08	101.0	-3.062	-0.111
10222 000207	Kabelkanal links (K70 aus E270) nicht umgesetzt, s = 40 cm, Gleisbau	5403607.11	5403607.11	101.0	-3.276	-0.106
10228 001106	Kabelkanal links (K70 aus E270) nicht umgesetzt, s = 40 cm, Gleisbau	5403608.15	5403608.15	101.0	-2.209	-0.127

Transparent Data and Documentation

BACKOFFICE

1. Categorized Point Cloud
2. Inventory – geo-data package
3. Updated drawings
4. Reports

02 Inventory as a Service

Makes more use of the Point Cloud



Inventory as a Service

Doing the counting ...

Automatic Detection in (driving-) images



Automatic extraction of individual objects as point cloud



Objekte erfassen - Übersicht						
Station (Trasse)	Beschreibung	Rechtswert	Hochwert	Höhe	Abstand (Streifen)	Höhendifferenz z
50156.878787	✓ Beginn Kabelkanal links (KTB aus ESTW noch nicht umgesetzt) , b = 40 cm, Gleisa	3463665.87	5526469.48	87.8	-3.588	-0.124
50182.981251	✓ Kabelkanal links (KTB aus ESTW noch nicht umgesetzt) , b = 40 cm, Gleisabstand	3463666.76	5526495.57	87.68	-3.295	-0.249
50183.993725	✓ Kabelkanal links (KTB aus ESTW noch nicht umgesetzt) , b = 40 cm, Gleisabstand	3463665.57	5526496.61	87.92	-4.509	-0.01
50185.101869	✓ Kabelkanal links (KTB aus ESTW noch nicht umgesetzt) , b = 40 cm, Gleisabstand	3463665.59	5526497.72	87.9	-4.515	-0.029
50186.349948	✓ Kabelkanal links (KTB aus ESTW noch nicht umgesetzt) , b = 40 cm, Gleisabstand	3463666.81	5526498.94	87.51	-3.323	-0.418
50208.160749	✓ Ende Kabelkanal links (KTB aus ESTW noch nicht umgesetzt) , b = 40 cm, Gleisabs	3463667.09	5526520.751	87.4	-3.552	-0.511
50208.18051	✓ Beginn Kabelkanal links (Neu), b = 40 cm, Gleisabstand XX m	3463667.08	5526520.771	87.4	-3.562	-0.511
50212.468404	✓ Kabelkanal links (Neu), b = 40 cm, Gleisabstand 3.71 m	3463667.03	5526525.061	87.5	-3.712	-0.408
50213.759901	✓ Beginn Kabelkanal links , b = 30 cm, Gleisabstand XX m	3463667.53	5526526.341	87.55	-3.242	-0.357
50215.349205	✓ Kabelkanal links (Neu), b = 40 cm, Gleisabstand 3.73 m	3463667.08	5526527.941	87.51	-3.73	-0.396
50222.892907	✓ Kabelkanal links , b = 30 cm, Gleisabstand 3.28 m	3463667.71	5526535.471	87.52	-3.275	-0.38
50238.931196	✓ Kabelkanal links , b = 30 cm, Gleisabstand 3.21 m	3463668.15	5526551.501	87.51	-3.209	-0.377


03 Slab-track Measurements

Geometric stability offers prediction based on micro-changes



Slab-track Measurements



Track Geometry: minimum settlement and deformation



The slab track system ensures exceptional geometric stability over time, minimizing settlement and deformation compared to ballast track.

Slab-track Measurements


Track Geometry: subtle trends allow for prediction



By increasing measurement frequency, even subtle trends in track geometry can be identified before they evolve into faults.

Slab-track measurements and inspections

Track Geometry: patterns for future deterioration



Through data analysis and predictive insights, each measurement becomes a signal of the track's future condition revealing patterns and deviations.

04 Slab-track Inspection

2 Case Studies: EUROTUNNEL and ELIZABETH LINE



Case Study 1: Eurotunnel

Plasser & Theurer

Automated Video Inspection



Case Study 1: Eurotunnel

Automated Video Inspection



Infrastructure

- 50 km of railway running through an underwater tunnel
- 80 km of railway running in open-air sections

Track System


- Ballastless slab track used in all tunnel sections
- Analysis of 660,000 fasteners

Monitoring

- 100km/h measurement speed
- 4 inspecting linear cameras

Case Study 1: Eurotunnel

Automated Video Inspection



Case Study 1: Eurotunnel

Automated Video Inspection

Values

Run: 114058

Date: 18/12/18

Time: 23:10

Current speed: 18.08 km/h

Current direction: Forward

Total length: 18 + 077

Left Camera

Left - Inner Railbed

Right Camera

Right - Inner Railbed

Left Camera

Left - Outer Railbed

Right Camera

Right - Outer Railbed

Type	Category	Created	FE	Site	Comment	Creation day
Main Track - Fastener - Soft missing	Info	A	18.08.18	Right - Outer		18.12.2018 23:10:58
Main Track - Fastener - Soft missing	Info	A	18.08.18	Left - Outer		18.12.2018 23:10:58
Main Track - Fastener - Soft missing	Info	A	18.08.18	Left - Outer		18.12.2018 23:10:58
Main Track - Fastener - Soft missing	Info	A	18.08.18	Left - Outer		18.12.2018 23:10:58
Main Track - Fastener - Broken insert	Info	A	18.08.18	Left - Outer		18.12.2018 23:10:58
Main Track - Fastener - Soft missing	Info	A	18.08.18	Right - Outer		18.12.2018 23:10:58
Main Track - Fastener - Soft missing	Info	A	18.08.18	Right - Outer		18.12.2018 23:10:58
Main Track - Fastener - Broken insert	Info	A	18.08.18	Right - Outer		18.12.2018 23:10:58
Main Track - Fastener - Broken insert	Info	A	18.08.18	Left - Inner		18.12.2018 23:10:58
Main Track - Fastener - Broken insert	Info	A	18.08.18	Left - Inner		18.12.2018 23:10:58

Case Study 2: Elizabeth Line

Plasser & Theurer

The IMV, Multi-inspection Vehicle



Picture by © Transport of London – All rights reserved.



DMA Diagnostics
A Plasser & Theurer Company

Case Study 2: Elizabeth Line

The IMV, Multi-inspection Vehicle



Infrastructure

- 100 km total route, including 42 km of new twin tunnels under central London
- Designed to increase central London rail capacity by 10%

Track System


- Ballastless slab track throughout tunnel sections
- Floating slab track in sensitive areas to mitigate noise and vibration

Monitoring

- Routine track inspection with dedicated vehicle;
- TracksNet software suite for multi-source data collection and analysis.

Case Study: Elizabeth Line


Asset-specific defect identification – High-precision



Case Study: Elizabeth Line

Plasser & Theurer

Assets Virtual Inspection



05 One Stop Shop

We offer a System or “as a Service”



One Stop Shop offering

Riegl VMX System

- IMU (Inertial Measurement Unit)
- GNSS (Global Navigation Satellite System)
- DMI (Distance Measuring Instrument)
- 3 Lidars (360° 3D Laser scanner)
- 2 Colour cameras (high resolution RGB)

Fleet of 14 Measurement vehicles in Europe and US

- Fully equipped and calibrated measurement car
- Provided under full track usage approval management
- All DMA Geometry and Vision Inspection Systems operational
- Ultrasonics, Eddy Current and Georadar upon request



From a single system to a fully-fledged fleet

Plasser Diagnostics Systems

Self-propelled or towed measurement vehicles up to 160 km/h and stand-alone up to 350 km/h systems*:

- ⚙ Track Geometry Measurement
- ⚙ Turnouts and Crossing Measurement
- ⚙ Rail Profile Measurement
- ⚙ Corrugation Measurement
- ⚙ 3rd (power) Rail Measurement
- ⚙ Catenary Wear- and Position Measurement
- ⚙ Clearance and Tunnel Inspection
- ⚙ Track Component Video Inspection
- ⚙ Top-of-rail and rail-web Video Inspection
- ⚙ Catenary Video- and Infrared Inspection
- ⚙ Driver's View Video Inspection
- ⚙ Ultrasonic Rail Inspection
- ⚙ Ground Penetrating Radar Track Inspection





Stefan Damm
CEO

DMA s.r.l.

Via Andorno, 22
10153 Torino (TO) | Italy

M +39 342 7808 125
E-Mail sdamm@dmatorino.it



Jochen Nowotny
CEO

Track Machines Connected

Regensburger Strasse 3
4020 Linz | Austria

M +43 676 843243 600
E-Mail jochen.nowotny@tmconnected.com